



## Projects Portfolio

Pooyan Latifi

Senior Mechanical Engineer

Mechanical Engineering Consultant

---

SECTION-1 Major EPC projects

SECTION-2 Brownfield and manufacturing projects

**SECTION-1**  
**Major EPC projects**

---



# Azar Oil Field Development-Central Processing Facility (CPF)

The **Azar oil field**, situated in Ilam Province along the Iran-Iraq border, is geologically complex and one of the region's most challenging onshore fields. The CPF development encompassed **engineering, procurement, construction, and commissioning**, with the goal of achieving normal operations at **65,000 barrels of oil per day (BOPD)**.

As Lead Mechanical (static) engineer working at EPC Joint Venture for delivery of CPF, I was responsible for :

- Leading on time delivery of mechanical scope's deliverables including technical specs, mechanical datasheets, and MRs for fixed and packaged mechanical equipment
- Clarification with vendors, generate TBE for the separator, air coolers, and storage tanks.

The project met and exceeded contractual oil production targets (65,000 BOPD), laying groundwork for further expansion.



# South Pars Gas Field Development Phases 13, 15–16, and 20–22 | Engineering & Procurement services

The **South Pars Gas Field** is the world's largest gas-condensate field, jointly shared between Iran and Qatar. Each development phase is designed to produce **2 billion cubic feet of natural gas per day** (~56 million m<sup>3</sup>/day), along with significant volumes of **ethane, LPG, condensate, and sulfur**.

## **Project Scope:**

### **Phase 13**

Full-scale gas processing and export facilities, producing sales gas, condensate, and LPG.

### **Phases 15–16**

Onshore processing capacity of **2,000 MMSCFD**, including condensate stabilization, MEG regeneration, sulfur recovery, LPG storage, and utility systems.

### **Phases 20–22**

Similar scope to Phases 15–16, with added capacity for **75,000 bpd condensate** and **3,000 tons/day LPG**, designed for domestic consumption and export.



# South Pars Gas Field Development Phases 13, 15–16, and 20–22 | Engineering & Procurement services

## My Role & Contributions:


### Phases 13, 20-24

- Leading detailed engineering activities including vendor documents review/approval for the Waste Effluent Disposal and Network - Unit 129
- Calculation and engineering drawing preparation for more than 10 columns and API-650 storage tanks

### Phases 15-16

- Final review and approval of vendor documents for API-650 aboveground storage tanks

UNIT NO.	DESCRIPTION	PROJECT NO.	DATE	REV.	BY	CHK.	APPROVED	REVISIONS
13	WASTE EFFLUENT DISPOSAL NETWORK	13000	2013	1	...	...	...	...
15	WASTE EFFLUENT DISPOSAL NETWORK	15000	2015	1	...	...	...	...
16	WASTE EFFLUENT DISPOSAL NETWORK	16000	2016	1	...	...	...	...
20	WASTE EFFLUENT DISPOSAL NETWORK	20000	2020	1	...	...	...	...
21	WASTE EFFLUENT DISPOSAL NETWORK	21000	2021	1	...	...	...	...
22	WASTE EFFLUENT DISPOSAL NETWORK	22000	2022	1	...	...	...	...



**GENERAL NOTES**

- 1- ALL DIMENSIONS SHOWN ON THIS DRAWING SHALL BE CONSIDERED AS A MINIMUM UNLESS OTHERWISE SPECIFIED. MANUFACTURER SHALL CONSULT WITH THE ENGINEER FOR ANY DIMENSIONAL CHANGES REQUIRED.
- 2- ALL DIMENSIONS ARE TO BE TAKEN FROM THE CENTERLINE UNLESS OTHERWISE SPECIFIED.
- 3- V/A/F FACTOR FOR LOADS COMBINATION HAS BEEN TAKEN AS 1.0.
- 4- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.
- 5- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.
- 6- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.
- 7- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.
- 8- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.
- 9- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.
- 10- WIND LOADS SHALL BE TAKEN AS PER THE DESIGN SPECIFICATION.

**SOUTH PARS GAS FIELD DEVELOPMENT**

**PHASES 13, 15 & 16**

**ASB/ALY/BEH/BAH**

**ARABIAN PETROLEUM COMPANY**

# Lorestan & Mahabad Petrochemical Project | Engineering & Procurement services

The Lorestan Petrochemical Complex is one of two affiliated plants (alongside Mahabad) under Bakhtar Petrochemical Company (BPC), situated along the Western Ethylene Pipeline. Nargan partnered with Italy's Technimont to deliver these projects.

## Each complex is designed to produce:

- 300,000 tons/year of LLDPE (Linear Low-Density Polyethylene)
- 300,000 tons/year of HDPE (High-Density Polyethylene)
- 30,000 tons/year of Butene-1

## My Role & Contributions:

- Review and approval of vendor documents for more than 40 ASME and PD5500 pressure vessels (three vendors)



# Tank Farm and Oil Depot Projects

## My Role & Contributions:

- Engineering Project Manager for “ Five cities strategic oil depots development project”
- Preparation of technical specs, procedures, calculation, and shop fabrication drawings for more than 50 fixed, floating and internal floating API 650 storage tanks
- Developed in-house software (Excel spreadsheet and VBA) for storage tank calculation





# AirTrunk MEL01 Datacenter-Commissioning

## My Role & Contributions:

- Commissioning Engineer representing BVPI (Commissioning Contractor) on-site
- Conducted L2/L3 inspection for :
  - CHW Flow and return piping
  - Cooling water pumps
  - FWU
  - HRU
  - Side stream filtration pump and dosing system

**AGCoombs** | 28 Colchester Road, Moorabool VIC 3189, Australia T: +61 3 9248 2702 F: +61 3 9248 2712

**TEST SHEET - COOLING TOWER**

CONTRACT NO. 1009  
 PROJECT NAME AirTrunk Datacenter - Phase 4A  
 SYSTEM ATML1-0010- HRU E01  
 UNIT LOCATION Data Hall Roof  
 DATE OF TEST TESTED BY

Contractor Name: ATML1-0010- HRU E01  
 Manufacturer: Embraco  
 Model No: ATWBH 12 2008 C34  
 Serial No: 20 400302

**FAN NAMEPLATE**  
 Item Type: Pulley Diameter (mm):  
 Shaft Centre (mm):  
 Tagpart No:

**MOTOR NAMEPLATE**  
 Manufacturer Model:  
 Frame / Class: P20X  
 Pulley Diameter (mm):  
 Shaft Size (mm):  
 Tagpart No:  
 Shaft Centre (mm):  
 I.P.A. 2000  
 VFD (Hz) 220V  
 VFD (Hz) 100V  
 VFD (Hz) 400V

**TEST RESULTS**

TEST RESULTS	DESIGN	FINAL	DESIGN	FINAL	DESIGN	FINAL
Flow						
Amperage						
Water Basin Temp Support						
Inverter Set Point						

**NOTES:**  
 - Fan complete is not accessible. (A complete pc to be provided later)  
 - To return to be revised to reflect correct design data.



**AIRTRUNK** | **Built.**


**Approval Signatures**

The above equipment and/or systems have been tested properly. The checklist items are complete and have been checked off only by parties having direct knowledge of the event, as marked below, respective to each responsible contractor. The equipment is now ready for packaging and shipping.

This test is submitted for approval, subject to an attached list of outstanding items yet to be completed. A Statement of Correction will be submitted upon completion of any outstanding areas. None of the outstanding items preclude safe and reliable testing being performed.

Company	Test Name	Signature	Date
AGC	MICHAEL	[Signature]	8/10/20
EMBRACO	MICHAEL	[Signature]	2/16/20
AGC	JOSH	[Signature]	8/10/20
AGC	ALLEN	[Signature]	5/6/20
BUILT	ALLEN	[Signature]	8/19/20

**External Reference**



**AIRTRUNK** | **Built.**

**Procedure**

DESCRIPTION	PASS	FAIL	N/A	COMMENT
<b>Tasks by Others (requires milestones and work from other trades) Parallel works with service providers - Controlworks / AG Coombs</b>				
<b>Requires Water Supply (to basin)</b>				
1. Check all grass, oil, dirt and debris is removed	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
2. Flush the cold water basin to remove sediment	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3. Remove strainer screen and clean	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Requires Power to Pump (DOL)</b>				
4. Verify water treatment plan has been implemented	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Refer to AGC records
5. Verify passivation has been implemented	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Refer to AGC records
6. Manually fill the cold-water basin to the overflow connection	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Refer to AGC records
7. Check for proper spray water pump rotation	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Refer to AGC records
8. Record voltage and current across pump motor	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Refer to AGC records
Amp draw: 9.6 Amp Voltage: 420V	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Requires Power to Fan (via VFD)</b>				
10. Check minimum speed settings for variable frequency drives	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
11. Verify fan(s) is rotating in proper direction	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
12. Record voltage and current across fan motor	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
13. Amp draw: Voltage:	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Requires Field Wiring and Water Supply to Solenoid</b>				
14. Fill basin to proper operating levels (check work by others)	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
15. Check operation of Electronic Water Level Controller	Yes	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Will be checked through BMS

**From AGC records:**  
 { 420V } 9.9 Amp, 9.6, 9.6 Amp ID: HRU-SPE01  
 { 420V } 9.7A, 9.5, 9.5 Amp ID: HRU-SPE02  
 { 0.02 bar } 9.13 Amps c. out 25 Amps



## SECTION-2 Brownfield and manufacturing projects



# Eastern Treatment Plant Power Station-Coolant PRV Tank

- Concept Design
- Detailed Design
- SiD Workshop
- Fabrication shop drawings review/approval
- Vendor QA/QC documents review/approval




# Eastern Treatment Plant Power Station- Pre/post Ozone piping spools

- Piping technical spec
- Detailed Design
- SiD Workshop
- Fabrication shop drawings review/approval
- Vendor QA/QC documents review/approval



# Winneke Treatment Plant –Supernatant pumps FRA panel

- Design Management
- Basic Design
- Vendor documents review/approval
- FAT
- SiD Workshop
- Commissioning Technical support



# Yering Gorge Pump Station—PRV replacement

- Design Management
- PRV capacity calculation and valve selection
- SOW and vendor engagement
- SiD Workshop
- Pipework concept design
- Pipework vendor documents review/approval
- Execution Technical support



# TEAM Inc. – Leak Seal

## About TEAM Inc.

TEAM Inc. is a global leader in on-stream leak sealing and asset integrity management services for the oil, gas, petrochemical, and power sectors, providing engineered solutions that minimize downtime and enhance plant safety.

## My Role & Achievements



- Delivered **100+ custom leak seal enclosure designs** for pressurized piping and equipment.

Designs completed in compliance with **ASME PCC-2**, **ASME VIII Div.1**, and **ASME B31.3**.

- Prepared **engineering calculations, datasheets, and fabrication drawings**, and coordinated with vendors/fabricators.
- Provided **technical and installation support**, ensuring every design was successfully fabricated and installed.

## Outcome


Safe, reliable on-stream leak sealing solutions, reducing production losses and maintaining asset integrity.



# Air Cooled heat exchanger


## Detailed Design

- Thermal design of the coil
- Hydraulic calculations and plenum sizing
- Fan selection
- Pressure and strength calculations
- Structural support design
- Fabrication shop drawings
- Quality Control documentation



## Project Management

- Fan Procurement
- Fabrication supervision and support
- Budget and schedule monitoring
- Shipment to site



# Shell & Tube and Tube bundles

## Detailed Design

- Thermal design review
- Pressure vessel calculations –AS1210
- Tubeplate calculations-AS3857
- Fabrication shop drawings
- Fabrication Procedure
- Quality Control documentation

## Production Management

- Tube plates, and special items procurement
- Fabrication supervision and support
- Schedule monitoring
- Shipment to site




# Boiler Economizers

## Detailed Design

- Sizing based on Boiler model and capacity
- Thermal design
- Pressure vessel calculations –AS1210
- Fabrication shop drawings
- Quality Control documentation

## Production Management

- Leading 3<sup>rd</sup> party inspection and design verification
- Plant registration
- Special items procurement Fabrication supervision and support
- Schedule monitoring
- Shipment to site




# Air Handling Units

## Detailed Design

- Thermal and design of the cooling coil
- Hydraulic calculations and duct sizing
- Mechanical strength calculations to AS1210
- Fabrication shop drawings
- Quality Control documentation

## Project Management

- Subcontractors' management
- Fabrication supervision and support
- Budget and schedule monitoring
- Shipment to site




# Special Heat Exchangers

## Detailed Design

- Thermal design
- Pressure vessel calculations –AS1210
- Fabrication shop drawings
- Quality Control documentation

## Production Management

- Leading 3<sup>rd</sup> party inspection and design verification
- Plant registration
- Special items procurement Fabrication supervision and support
- Schedule monitoring
- Shipment to site




# Heat Recovery-Veolia-SA

- Hydraulic calculations
- Transmission Detailed design
- Fabrication supervision



# Diesel Genset Enclosure and fuel system - Flemington Racecourse

- Detailed Design
  - Fuel Tank and piping design – AS1940
  - Air requirements calculations – AS1668.2
  - Exhaust Pressure drop calculations
  - Attenuator and muffler detailed design
  - Acoustic louvre detailed design
  - Structural calculations and shop drawings
- Project Management
  - Procurement
  - Sub-contactor management
  - Fabrication supervision and support
  - Budget and schedule monitoring
  - Shipment and installation



# Diesel Genset Enclosure and fuel system – Cummins WA

## Detailed Design

- Fuel Tank and piping design – AS1940
- Air requirements calculations – AS1668.2
- Exhaust Pressure drop calculations
- Attenuator and muffler detailed design
- Acoustic louvre detailed design
- Structural calculations and shop drawings

## Project Management

- Procurement
- Sub-contactor management
- Fabrication supervision and support
- Budget and schedule monitoring
- Shipment and installation



# 530 Collins street- New Diesel Gen Exhaust and fuel system

## Detailed Design

- Exhaust piping detailed design
- Air requirements calculations – AS1668.2
- Exhaust Pressure drop calculations
- Special exhaust one way plenum design
- Acoustic louvre detailed design

## Project Management

- Procurement
- Sub-contactor management
- Fabrication and site installation supervision and support
- Budget and schedule monitoring



# Collie Power Station - Caustic Tank Hatch New Manhole

As project engineer, I was responsible for:


- Review/ approval of the design sub-contractor fabrication drawing
- Engagement and supervising tank cleaning , and cladding sub-contractors
- Developing SOW and choosing contactor for the fabrication and installation
- Conduct risk assessment, review JSA and execution supervision
- Project budget and schedule monitoring



# Collie Power Station – SDCC Seal upgrade project

As project engineer, I was responsible for:

- Conducted investigation to understand root cause of the constant failure and established design criteria for the upgrade replacement.
- Engaged and worked with Europe based R&D team of an international vendor to produce a solution.
- Handed over the proposed solution to the asset management team



# Collie Power Station – Fire pumps upgrade

Investigations and tests conducted by several fire consultants reveal that the existing fire protection system for conveyors B1& B2 and tripper gallery would not operate effectively in the event of a fire. A CAPEX project was initiated to rectify this issue. Leading the feasibility study stage as project engineer :

- Studied existing fire pumps spec
- Contacted OEM in US to request missing technical info such as performance curves
- Calculated new pumps' requirement to comply with AS2941-2008 Australian standard for fixed fire protection installations-Pumpset systems.
- Established SOW for next phase of the project.

## c) Pumps Requirement

The minimum requirement to make the current fire system functional is 3391 l/m @ 700 kpa at ground level deluge valve according to WP hydraulic calculation. Pressure loss from this point to electrical pump discharge point is calculated using Hazen-Williams equation and the results are summarised as below:

Pipe ND	Pipe length (m)	Number of fittings	Number of valves	Equivalent pipe length for fitting and valves(m)	Pressure loss per meter of the pipe (Kpa/m)	Pressure loss in total length of the pipe(Kpa)
250	120	6	5	110	0.0614	14
200	220	11	5	66	0.114	9
150	5	3	1	15	0.74	15


This method is suggested by AS 2118.1

$$P = 6.05 \times \frac{Q^{1.85}}{C^{1.85} \times d^{4.87}} \times 10^7$$

---

### 2000 G.P.M. 912 SERIES 50 HERTZ ELECTRIC MOTOR DRIVE

Section **912** Page **615**  
Date **April 2000**  
Supersedes Section 912 Page 615  
Dated August 1992



52  
to  
94  
P.S.I.

